Stula Enterprises
362 Wawecus hill rd.
Norwich Ct. 06360

Proposal

Proposal Date: 2/18/2022
Proposal #: 187
Project: Bacon Day tank

Bill To:
Town Of Colchester
Colchester Ct. 06415

HIC # - HIC.0645245
Electrical # - ELC.0203255-E1
Septic # - 006267
Piping # - PLM.0288885-P7

Phone:	E-mail
860-639-1351	Shawn@StulaLLC.com

Description	Rate	Total
Labor and materials for installation of new 75 gallon day tank for generator, Price includes the following - Alarm, combination – high / low fuel level - Alarm relay, for remote signal - Lead detection, double wall, plus alarm and P/M shutdown - Vent kit with caps & fittings, double wall, 3” NPT - Control panel cover, NEMA 1, duplex pumps and motors - Reverse flow controls & piping, 1/2” plumbing - Pump, cast iron, 4.0 GPM reverse fuel flow - Pump, cast iron, 2.0 GPM fuel supply - Motor, 1-phase 1/3 HP, 115VAC, 60Hz - Enclosure, NEMA 1 control panel cover - Warranty, manufacturer standard - Installation of new return piping back to tank - Installation of required piping and electrical work Limitations - Any and all permit fees are not included in price - Any code violations in existing piping and electrical that we will be tying into, If anything is discovered it will be brought to owners attention and work to be continued on a time and materials basis - If underground tank is deemed unsafe to tie into by plumbing subcontractor during the job this would be brought to the owners attention and decision would be made on how to continue with project, However materials purchased, such as daytank, ect. would still be required to be paid by the town and would be delivered to and left on site. - There is existing pollution on site and Stula enterprises is not responsible for any past, present, or future cleanup associated with this site. *** Town may want to have generator maintained company on site the day of start up to bleed fuel system and make sure everything is running as required ***	28,995.00	28,995.00

Subtotal	$28,995.00
Sales Tax (6.35%)	$0.00
Total	$28,995.00